	PART - B				
1	Supplying of 150mm dia pump set confirming to IS 8034:1989 AND i.s. 9283/1995 with latest amendements texmo, taroo equivalent brnazd with sepcified duty conditions and acesories 8034/2002. (Control panel board indoor type unit IS : 5124. above 10 HP to 20 HP		4	10000.00	Rupees Ten Thousand Only
2	Supplying and fixing mainature circuit breakers on existiong MCB distribution boards using necessary fixing materilas, and C type curve, indicator ON / OFF energy cross 3 with short circuit breaking capacity of 10 K and Complete wiring as required.		25	1005.00	Rupees One Thousand Five Only
3	Fabricating supplying and mounting MS cox of 16 SWG suitable for floor / wall mounting, fully weather proof with providion for better heat discription, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished 2 coats of red oxide primer paint and finally finished with approved colour enamelled metal paint etc,. complete box of 21600 cc or and Rs. 0.33				
			246500	0.37	Rupees Zero & Thirty seven Paise Only
4	Supplying and drawing 3 core flat PVC sheahted submersible pump cable manufactured with elecrolytic grade copepr with flexible copper conductor confirming to table 3 class 5 of IS : 8130-1984 and virgin grade PV insulation and sheathed suitable for working voltage up to 11.00 Volts				
		Rmtr	2000	159.50	Rupees One hundred Fifty nine & Fifty Paise Only
5	Supplying of L.T. UG Cable having aluminum conductor PVC insulated, sheathed, galvanized steel wire / steel tap armoured cable with PVC outer sheathing. 1.1. K.V.				
		Rmtr	200	236.50	Rupees Two hundred thirty six & fifty paise Only
6	Digging of trench of 0.6m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc., complete (as per civil				
		Rmt	150	80.00	Rupees Eighty only
7	Labour charge for laying of 1.1 KV class UG cable in existing trench GI pipe / stone ware pipe / on wall / on pole as required.				
		Rmt	200	8.00	Rupees Eight Only
8	Supplying of 150mm dia pump set confirming to IS 8034:1989 AND i.s. 9283/1995 with latest amendements texmo, taroo equivalent brnazd with sepcified duty conditions and acesories 8034/2002. 10HP /20 Stage				
	10 HP / 20 Stage	Nos.	3	37000.00	Rupees Thirty seven thousand Only

Signature of the Contractor

Executive Engineer